

BIDS AND AWARDS COMMITTEE

BID BULLETIN No. 9 s. 2022

22 April 2022

Projects:

Negotiated Procurement:

1. Supply and Delivery of Aluminum Sulfate and Liquid Chlorine

Competitive Bidding:

2. Fire Alarm and Detection System (Supply and Installation)
3. Upgrading of Power Supply: Two Sets of Generator Housing
4. Construction of Standard Factory Building: Retaining Wall for SFB No.17

Date of Bid Opening: 10 May 2022

TO ALL PROSPECTIVE BIDDERS:

No.	Project	Inquiry/Clarifications	Response
1	Fire Alarm and Detection System (Supply and Installation)	<p>Is site inspection required for this project?</p> <p>When will the bidding requirements as specified in the TOR item 4.0 be submitted?</p> <p>Who shall provide the single line diagram system?</p> <p>Based on the given floor plan layout the below fire alarm devices are not reflected. Please provide the specific locations of each devices:</p> <p>a. Fire Alarm Control Panel</p>	<p>Site inspection is required for this project.</p> <p>It will be submitted on or before the day of the bid submission, 10 May 2022, 9:30 AM.</p> <p>The winning bidder shall provide the single line diagram system plan.</p> <p>a. Fire Alarm Control Panel shall be installed at the 5th floor at the Command Center Office</p> <p>b. LCD Repeater shall be place in the lobby near the Information Desk</p> <p>c. Digital optical detectors with remote indicator are marked as "o" in the plan layout.</p>



No.	Project	Inquiry/Clarifications	Response
		b. LCD Repeater c. Digital Optical Detector w/ remote indicator d. Beam Detector e. Manual Pull Station f. Sounder with beacon strobe g. Input and Output Modules	d. Beam Detector shall be place in the Auditorium e. Manual Pull Stations are marked as "M" in the plan layout. f. Sounder with beacon strobe shall be placed near the manual call point g. Input and output modules depend on the single line diagram
2	<i>Construction of Standard Factory Building: Retaining Wall for SFB No.17</i>		Bill of Quantities (BOQ) Item no. 4.4 - Supply and Installation of CHB with Plastering and Reinforcements Unit of Measurement from kgs. to sq.m. (Please see revised BOQ as Annex A)
3	<i>Supply and Delivery of Aluminum Sulfate and Liquid Chlorine</i>	Review of price of aluminum sulfata	No Change in the ABC

All terms, conditions and instructions to bidders specified in the Bidding Documents inconsistent with this Bid Bulletin are hereby superseded and modified accordingly.

For guidance and information of all concerned.



CHARLES M. RAMONES
 BAC-Chairperson

(Name of Company of Prospective Bidder)
(Address of Prospective Bidder)

BILL OF QUANTITIES

Contract Name : Construction of Standard Factory Building: Retaining Wall for SFB 17
 Location of Contract : Phase II, Freeport Area of Bataan, Mariveles, Bataan
 Project Duration : 40 C.D.
 Required Equipment : One-bagger Cement Mixer Backhoe
 Dump Truck

Item No.	Description	Unit	Quantity	Unit Price	Amount
(1)	(2)	(3)	(4)	(5)	(6)
I FACILITIES FOR THE ENGINEERS					
1.1.	Provision of Progress Photographs <i>Provision for Progres Photographs</i>	e.a.	100.00	in words :	in words :
				in figures :	in figures :
II OTHER GENERAL REQUIREMENTS					
2.1.	Occupational Safety and Health Program	days	40.00	in words :	in words :
				in figures :	in figures :
2.2.	Mobilization/Demobilization	l.s.	1.00	in words :	in words :
				in figures :	in figures :
2.3.	Project Billboard and Signboard <i>Includes the following:</i> <i>Safety Signages</i> <i>PPE's</i> <i>Medicine kits</i>	e.a.	1.00	in words :	in words :
				in figures :	in figures :
Total for this page					₱

Name and Signature of Bidder

Name of Company

III EARTHWORK					
3.1.	Clearing and Grubbing	cu.m	126.00	in words :	in words :
				in figures :	in figures :
3.2.	Excavation	cu.m.	117.48	in words :	in words :
				in figures :	in figures :
IV SLOPE PROTECTION STRUCTURES					
4.1.	Formworks <i>* Used Good Lumber and 1/2" for Plywood</i>	lot	1.00	in words :	in words :
				in figures :	in figures :
4.2.	Concreting Works <i>See plans - Used : Concrete Designed Mixed A</i>	cu.m.	37.97	in words :	in words :
				in figures :	in figures :
4.3	Supply and Installation of Reinforcements <i>See plans</i>	kgs.	3,211.66		
4.4	Supply and Installation of CHB with Plastering and Reinforcements <i>See Plans : Used Load Bearing Concrete Hollow Blocks 750psi with 16mm thick plaster</i>	sq.m.	317.36	in words :	in words :
				in figures :	in figures :
<i>Total for this page</i>					₱
TOTAL AMOUNT					₱

Name and Signature of Bidder

Name of Company